

Old and New Business 4-14-26

- **Blending events** – Recent snow melt and heavy rainfall have resulted in influent flows in excess of the 26 MGD forward flow capacity at the WWTF. This resulted in the first blending events of 2026.

The first was Thursday April 2 and began about 8PM and concluded around 2:30AM the morning of April 3rd. The daily influent flow was 17.635 mgd with 1.056 mgd requiring blending.

Starting on 4/4 a total of 19.029 mgd was treated with 0.102 mgd being blended the first few hours of the day.

Rainfall again arrived on already saturated grounds during the overnight hours last Friday resulting in another blending event that began about 4:15AM Saturday morning. The plant processed a total of 27.064mgd with 4.706 mgd being the blended volume.

- **PFAS Update** – The next required effluent sample (6X/year) and the 2026 sludge sample (1X/year) have been collected and sent out for PFAS/PFOA analysis. The last effluent sample result came back acceptable.
- **Headworks project** - Donohue was on site on 4/7/26 and met with HOVMSD staff on progress and design of the headworks project. All plant staff participated as some months have passed since our last staff discussion and two employees were not yet employed when the original screening replacement options study was completed. The Donohue 30% project pdf file was distributed to the Commission via email on 4/9.
- **Filter Project** – With the red lined drawing turned over, Donohue has completed all project deliverables. The last step is the final reimbursement back to HOVMSD from the Clean Water Fund check arriving later this month.

Key Dates / Meetings

- 4/23 Virtual meeting with NEW Water – Permit reissuance discussion
- 4/28 Community meeting – Kaukauna
-